FRENCH ROCKS DIVISION.

ADVERTISEMENT.

The 24th October 1894.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, French Rocks Division, up to 15th November 1894, for improving and restoring the Belgunda Kallukere tank, Registered No. 137 of Nagamangala Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of January 1896.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's office at French Rocks, between the hours of 11 A. M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Improving and Restoring the Belgunda Kallukere, Registered No. 137, Nagamangala Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of Work.	Per.	Quantity.	Rate. Rs.	A.	P.	Total Cost.
Bund.						
Earthwork raising bund	C. Yds.	17,288				
Turfing front slope	Sqr.	125·25				
Old stone work with new jelli	C. Yds.	588				
New stone work	C. Yds.	2,720				
Grade stones	Each.	27				
B. M. stones	Each.	2				
Tank No. stone	Each.	1				
Gauge stone	Each.	1				
Total	..	..				
Sluice.						
Examining and repairing sluice	Lump sum Rs.					
Waste Weir No. I. LEFT WASTE WEIR, 100 FEET LONG.						
Benching rock for foundation	Lump sum Rs.					
Brick in surki mortar	C. Ft.	3,562				
Burnt stone slabs (dressed)	C. Ft.	177				
Plastering with surki mortar	Sqr.	16·54				
Dry stone work	C. Yds.	12				
Total	..	..				
Waste Weir No. II.						
Total as per Weir No. I	..	Rs.				
Scouring sluice	Lump sum Rs.					
Miscellaneous.						
Compensation for lands to be submerged	Lump sum Rs.					

T. INMAN,
Executive Engineer.